





01.05 PC Tie Beam Quantity Survey	Section: 03.00.03 - Cast In Place Concrete Plain Concrete with minimum of Compressive Strenght of -- Days of -- MPA accoring to specifications including all necessary Formwork,Isolation & Construction Joints,Additives,etc. according to specifications and drawings			
Level : (+98.30) PC Founadtion				
Villa Type A3				
Type	Count	Volume = Area * Cut Length		
		Cut Length (M)	Area (M2)	Volume (M3)
TB1 PC 600*300	1	3.30	0.18	0.594
TB1 PC 600*300	1	1.60	0.18	0.288
TB1 PC 600*300	1	1.08	0.18	0.194
TB1 PC 600*300	1	1.85	0.18	0.333
TB1 PC 600*300	1	3.80	0.18	0.684
TB1 PC 600*300	1	3.80	0.18	0.684
TB1 PC 600*300	1	1.60	0.18	0.288
TB1 PC 600*300	1	1.08	0.18	0.194
TB1 PC 600*300	1	1.48	0.18	0.266
TB1 PC 600*300	1	0.18	0.18	0.032
TB1 PC 600*300	1	1.85	0.18	0.333
TB1 PC 600*300	1	1.33	0.18	0.239
TB1 PC 600*300	1	2.20	0.16	0.360
TB1 PC 600*300	1	3.22	0.18	0.580
TB1 PC 600*300	1	3.95	0.18	0.711
TB1 PC 600*300	1	3.93	0.18	0.707
TB1 PC 600*300	1	0.06	0.18	0.010
TB1 PC 600*300	1	1.26	0.14	0.175
TB1 PC 600*300	1	1.26	0.14	0.175
TB1 PC 600*300	1	3.65	0.18	0.657
TB1 PC 600*300	1	3.65	0.18	0.657
TB1 PC 600*300	1	3.93	0.18	0.707
TB1 PC 600*300	1	4.15	0.18	0.747
TB1 PC 600*300	1	3.22	0.18	0.580
TB1 PC 600*300	1	1.35	0.18	0.243
TB1 PC 600*300	1	1.48	0.18	0.266
TB1 PC 600*300	1	1.33	0.18	0.239
TB1 PC 600*300	1	2.20	0.16	0.360
TB1 PC 600*300	1	0.18	0.18	0.032
TB1 PC 600*300	1	0.40	0.18	0.072
TB1 PC 600*300	1	1.35	0.18	0.243
TB1 PC 600*300	1	0.40	0.18	0.072
TB1 PC 600*300	1	0.08	0.18	0.014
TB1 PC 600*300	1	0.08	0.18	0.014
TB1 PC 600*300	1	0.06	0.18	0.010
TB1 PC 600*300	1	0.90	0.18	0.162
TB2 PC 600*300	1	3.70	0.18	0.666
TB2 PC 600*300	1	1.38	0.15	0.203
TB2 PC 600*300	1	2.11	0.18	0.374
TB2 PC 600*300	1	2.51	0.16	0.406
TB2 PC 600*300	1	2.10	0.18	0.378
TB2 PC 600*300	1	0.47	0.18	0.085
TB2 PC 600*300	1	2.11	0.18	0.374
TB2 PC 600*300	1	2.10	0.18	0.378
TB2 PC 600*300	1	1.38	0.15	0.203
TB2 PC 600*300	1	3.70	0.18	0.666
TB2 PC 600*300	1	2.51	0.16	0.406
Grand total	47			16.057



<u>GENERAL NOTES</u>			
<u>LEGEND</u>			
			
<u>KEY PLAN</u>			
<u>REVISION</u>			
No.	Description	Issued by	Revision Date
<u>PROJECT</u>			
<u>CLIENT</u>			
<u>CONSULTANT</u>			
<u>CONTRACTOR</u>			
<u>DRAWING TITLE</u>			
Quantity Surveyry-Cast in Place Concrete-Tie Beams PC			
Project Name	Duplex Villa Type A3		
Date	22-June-2025		
Drawn by	Eng/ Ahmed Yasser		
Checked by	Eng/ Ahmed Yahia		
DRAWING TITLE			
Scale	1 : 100		