



01.05 Slab On Grade Quantity Survey		Section: 03.01.05 - Cast In Place Concrete					
Level : (+99.90) S SOG							
Villa Type A3							
		Plain Concrete with minimum of Compressive Strenth of -- Days of -- MPA accoring to specifications including all necessary Formwork,Isolation & Construction Joints,Additives,etc. according to specifications and drawings					
Level	Type	Count	Volume = Thickness * Area			Notes	
			Area (M)	Thickness (M)	Volume (M3)		
(+99.90) S SOG	SOG 150 mm	1	319.53	0.15	47.929		



GENERAL NOTES

LEGEND



KEY PLAN

REVISION

No.	Description	Issued by	Revision Date

PROJECT

CLIENT

CONSULTANT

CONTRACTOR

DRAWING TITLE

Quantity Survery-Cast in Place Concrete - Slab On Grade

Project Name	Duplex Villa Type A3
Date	22-June-2025
Drawn by	Eng/ Ahmed Yasser
Checked by	Eng/ Ahmed Yahia

DRAWING TITLE

Scale	1 : 100
-------	---------